5'-0" ON CENTER MAX.

4" X 4" X 1/4" SQ TUBE
CAPPED INSIDE

HOMELAND VINYL
GORILLA WOOD SERIES
1" X 5-1/2" PVC DECKING
(COLOR TBD BY DESIGNER)

5/16"Ø X 1"
SS SHEET METAL SCREWS
(BUTTON HEAD)
(3/16"Ø HOLES IN POSTS)
6061-T6

AL L3" X 3" X 1/4"
PANEL FRAME TYP.
FOUR SIDES
6061-T6

3/4" BASE PLATE

GRADE

VARIES

VARIES

3'-0" MIN. HEIGHT OF SOLID INFILL

2"

ELEVATION VIEW

TYPICAL PANEL DETAIL